

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-22288-00-00
Spot: SWNESENE Sec/Twnshp/Rge: 20-33S-3E
3324 feet from S Section Line, 626 feet from E Section Line
Lease Name: SHORT NELSON Well #: 3-A
County: COWLEY Total Vertical Depth: 3295 feet

Operator License No.: 33608
Op Name: W.D. SHORT OIL CO., LLC
Address: 102 S RIVER RD PO BOX 729
OXFORD, KS 67119

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	10.75	209		350 SX
PROD 7		3294	877	150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/05/2011 8:00 AM
Plug Co. License No.: 34271 Plug Co. Name: KIVETT PLUGGING & PIPE PULLING, INC.
Proposal Rcvd. from: KENNETH KIVETT Company: KIVETT PLUGGING & PIPE PULLI Phone: (580) 363-3036

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 10/06/2011 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 3100', CONSOLIDATED OIL WELL SERVICES MIXED & PUMPED 25 SX CLASS A COMMON 2% CC AND DISPLACED IN CASING. TAGGED CEMENT @ 2975'. 10-6-2011, CUT CASING @ 877', LAYED DOWN 877' OF 7" CASING. RIH W/TBG @ 350', CONSOLIDATED OIL WELL SERVICES MIXED & PUMPED 170 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 10-6-2011, 5:00 PM. CONSOLIDATED CEMENT TICKET #33242.

Perfs:


Top	Bot	Thru	Comments
3294	3295	OH	

Remarks:

Plugged through: TBG

District: 02

Signed


(TECHNICIAN)

RECEIVED Form CP-2/3

NOV 02 2011 11/03/11

KCC WICHITA