

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-191-22153-00-00
Spot: NWSESESE Sec/Twnshp/Rge: 28-31S-1E
633 feet from S Section Line, 652 feet from E Section Line
Lease Name: SHORT Well #: 1
County: SUMNER Total Vertical Depth: 3600 feet

Operator License No.: 33608
Op Name: W.D. SHORT OIL CO., LLC
Address: 102 S RIVER RD PO BOX 729
OXFORD, KS 67119

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	264		140 SX
PROD	5.5	3598	2490	50 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/17/2011 8:00 AM
Plug Co. License No.: 34271 Plug Co. Name: KIVETT PLUGGING & PIPE PULLING, INC.
Proposal Revd. from: KENNETH KIVETT Company: KIVETT PLUGGING & PIPE FITTIN Phone: (580) 363-3036

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 10/18/2011 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 3550', CONSOLIDATED OIL WELL SERVICES MIXED & PUMPED 25 SX CLASS A COMMON 2% CC AND DISPLACED IN CASING. TAGGED CEMENT @ 3325'. CUT CASING @ 2490', LAYED DOWN 60 JOINTS 5-1/2" CASING (2490'). 10-18-2011, RIH W/TBG @ 320', CONSOLIDATED OIL WELL SERVICES MIXED & PUMPED 100 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 10-18-2011, 5:00 PM. CONSOLIDATED CEMENT TICKET #33292 & 33281.

Perfs:


Top	Bot	Thru	Comments
3552	3557	CSG	

Remarks:

Plugged through: TBG

District: 02

Signed


(TECHNICIAN)

RECEIVED Form CP-2/3

NOV 02 2011

11/03/11

KCC WICHITA