

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-02078-00-01
Spot: NWNWSENW Sec/Twnshp/Rge: 5-34S-6E
3903 feet from S Section Line, 3660 feet from E Section Line
Lease Name: RAHN UNIT 1 Well #: 6
County: COWLEY Total Vertical Depth: 2875 feet

Operator License No.: 33608
Op Name: W.D. SHORT OIL CO., LLC
Address: 102 S RIVER RD PO BOX 729
OXFORD, KS 67119

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	10.75	160		200 SX
PROD 6		2877		250 SX

Well Type: EOR UIC Docket No: E03386.1 Date/Time to Plug: 10/23/2011 8:00 AM
Plug Co. License No.: 34271 Plug Co. Name: KIVETT PLUGGING & PIPE PULLING, INC.
Proposal Rcvd. from: KENNETH KIVETT Company: KIVETT PLUGGING & PIPE PULLI Phone: (580) 363-3036

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 10/23/2011 8:00 AM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

DUMP SAND & SANDED BACK @ 2384'. RIH W/TBG @ 2200', CONSOLIDATED OIL WELL SERVICES MIXED & PUMPED 40 SX CLASS A COMMON 2% CC AND DISPLACED IN CASING. TAGGED CEMENT @ 1920'. TAGGED CEMENT ON BACKSIDE OF 6" @ 165'. RIH W/1" TBG @ 160', CONSOLIDATED OIL WELL SERVICES MIXED & PUMPED 140 SXS 60/40 POZMIX 4% GEL TO SURFACE. LAYED DOWN 1" TBG, RIH W/TBG @ 252', ESTABLISHED CIRCULATION, CONSOLIDATED MIXED & PUMPED 30 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 10-24-2011, 5:00 PM. CONSOLIDATED CEMENT TICKET #33324, & 33325.

Perfs:

Top	Bot	Thru	Comments
2875	2877	OH	Open-Hole
2138	2143	CSG	
2126	2128	CSG	

Remarks: E-03386

Plugged through: TBG

District: 02

Signed Duane Krueger
(TECHNICIAN)

cc to AIC
11/02/11
RECEIVED Form OP-2/3
NOV 02 2011
11/03/11
KCC WICHITA

DK