

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-035-19208-00-00  
Spot: SENWSW Sec/Twnshp/Rge: 21-33S-3E  
1698 feet from S Section Line, 4184 feet from E Section Line  
Lease Name: JOHNSON Well #: 8  
County: COWLEY Total Vertical Depth: 3283 feet

Operator License No.: 33608  
Op Name: W.D. SHORT OIL CO., LLC  
Address: 102 S RIVER RD PO BOX 729  
OXFORD, KS 67119

| String | Size  | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| SURF   | 6.625 | 2856       | 350         |          |
| COND   | 8.25  | 2424       | 350         |          |
| PROD   | 5.5   | 3230       | 350         | 150 SX   |

Well Type: OIL UIC Docket No: Date/Time to Plug: 10/12/2011 8:00 AM  
Plug Co. License No.: 34271 Plug Co. Name: KIVETT PLUGGING & PIPE PULLING, INC.  
Proposal Rcvd. from: KENNETH KIVETT Company: KIVETT PLUGGING & PIPE PULLI Phone: (580) 363-3036

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL  
Date/Time Plugging Completed: 10/14/2011 5:00 PM KCC Agent: DUANE KRUEGER

**Actual Plugging Report:**

RIH W/TBG @ 3200', CONSOLIDATED OIL WELL SERVICES MIXED & PUMPED 25 SX CLASS A COMMON 2% CC AND DISPLACED IN CASING. TAGGED CEMENT @ 2985'. SDON. 10-13-2011, CUT 8-1/4", 6-5/8", & 5-1/2" CASING @ 350', LAYED DOWN 350', ALL 3 STRINGS OF CASING. RIH W/TBG @ 350', CONSOLIDATED OIL WELL SERVICES MIXED & PUMPED 6 SXS GEL & 250 SXS 60/40 POZMIX 4% GEL. SDON. 10/14/2011, TAGGED CEMENT @ 150', RIH W/TBG @ 148', CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 225 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 10-14-2011, 5:00 PM. CONSOLIDATED CEMENT TICKET #33275 & 33277.

**Perfs:**


| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 3230 | 3283 | OH   |          |

Remarks:

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

RECEIVED

Form CP-2/3

NOV 02 2011

11/02/11

KCC WICHITA