

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-19264-00-00

Spot: NWSENW

Sec/Twnshp/Rge: 19-33S-3E

3818 feet from S Section Line, 3726 feet from E Section Line

Lease Name: HESKET

Well #: 5

County: COWLEY

Total Vertical Depth: 3215 feet

Operator License No.: 33608

Op Name: W.D. SHORT OIL CO., LLC

Address: 102 S RIVER RD PO BOX 729
OXFORD, KS 67119

String	Size	Depth (ft)	Pulled (ft)	Comments
--------	------	------------	-------------	----------

SURF	8.625	87		87 SX
------	-------	----	--	-------

PROD	5.5	3196		75 SX
------	-----	------	--	-------

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 10/04/2011 8:00 AM

Plug Co. License No.: 34271

Plug Co. Name: KIVETT PLUGGING & PIPE PULLING, INC.

Proposal Rcvd. from: KENNETH KIVETT

Company: KIVETT PLUGGING & PIPE PULLI

Phone: (580) 363-3036

Proposed
Plugging
Method:

AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER

Witness Type: PARTIAL

Date/Time Plugging Completed: 10/05/2011 5:00 PM

KCC Agent: DUANE KRUEGER

Actual Plugging Report:

Perfs:

RIH W/TBG @ 3100', CONSOLIDATED OIL WELL SERVICES MIXED & PUMPED 20 SX CLASS A COMMON 2% CC AND DISPLACED IN CASING. TAGGED CEMENT @ 2925', PERFORATED SQUEEZE HOLES @ 300'-301'. RIH W/TBG @ 300', CONSOLIDATED OIL WELL SERVICES MIXED & PUMPED 105 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCUALTED. PLUG DOWN 10-5-2011, 5:00 PM. CONSOLIDATED CEMENT TICKET #33240.

Remarks: CEMENT ALREADY ON BACKSIDE OF 5-1/2" @ 350'

Plugged through: TBG

District: 02

Signed

(TECHNICIAN)

RECEIVED

NOV 02 2011

KCC WICHITA

Form CP-2/3

11/03/11