

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-19263-00-00
Spot: SWSNW Sec/Twnshp/Rge: 19-33S-3E
3016 feet from S Section Line, 3637 feet from E Section Line
Lease Name: HESKET Well #: 3
County: COWLEY Total Vertical Depth: 3260 feet

Operator License No.: 33608
Op Name: W.D. SHORT OIL CO., LLC
Address: 102 S RIVER RD PO BOX 729
OXFORD, KS 67119

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	10.75	101		90 SX
PROD 7		3225		100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/04/2011 8:00 AM
Plug Co. License No.: 34271 Plug Co. Name: KIVETT PLUGGING & PIPE PULLING, INC.
Proposal Rcvd. from: KENNETH KIVETT Company: KIVETT PLUGGING & PIPE PULLI Phone: (580) 363-3036

Proposed Plugging Method: AS PRE KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 10/04/2011 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

Perfs:


RIH W/TBG @ 3100', CONSOLIDATED OIL WELL SERVICES MIXED & PUMPED 25 SX CLASS A COMMON 2% CC AND DISPLACED IN CASING. TAGGED CEMENT @ 2975'. PERFORATED SQUEEZE HOLES @ 350'-351'. RIH W/TBG @ 350', CONSOLIDATED OIL WELL SERVICES MIXED & PUMPED 75 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 10-4-2011, 5:00 PM. CONSOLIDATED CEMENT TICKET #33208.

Remarks: CEMENT ALREADY @ SURFACE ON BACKSIDE OF 7"

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

RECEIVED
NOV 02 2011
KCC WICHITA

Form CP-2/3

11/03/11

✓