

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-035-02122-00-00  
Spot: NWNWNESE Sec/Twnshp/Rge: 2-34S-5E  
2333 feet from S Section Line, 1081 feet from E Section Line  
Lease Name: HART Well #: 1  
County: COWLEY Total Vertical Depth: 3155 feet

Operator License No.: 33608  
Op Name: W.D. SHORT OIL CO., LLC  
Address: 102 S RIVER RD PO BOX 729  
OXFORD, KS 67119

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	107		90 SX
PROD	4.5	3135		125 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/21/2011 8:00 AM  
Plug Co. License No.: 34271 Plug Co. Name: KIVETT PLUGGING & PIPE PULLING, INC.  
Proposal Rcvd. from: KENNETH KIVETT Company: KIVETT PLUGGING & PIPE PULLI Phone: (580) 363-3036

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL  
Date/Time Plugging Completed: 10/21/2011 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 3100', CONSOLIDATED OIL WELL SERVICES MIXED & PUMPED 20 SX CLASS A COMMON 2% CC AND DISPLACED IN CASING. TAGGED CEMENT @ 2850'. PERFORATED SQUEEZE HOLES @ 250'-251'. RIH W/TBG @ 250', CONSOLIDATED OIL WELL SERVICES MIXED & PUMPED 20 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 10-21-2011, 5:00 PM. CONSOLIDATED CEMENT TICKET #33323.

Perfs:

Top	Bot	Thru	Comments
3135	3155	OH	

Remarks: CEMENT ON BACKSIDE OF 4-1/2" @ SURFACE

Plugged through: TBG

District: 02

Signed

Duane Krueger  
(TECHNICIAN)

RECEIVED

NOV 02 2011

KCC WICHITA

Form CP-2/3

11/03/11

1/4