

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-02119-00-00
Spot: NESWSWE Sec/Twnshp/Rge: 2-34S-5E
357 feet from S Section Line, 2256 feet from E Section Line
Lease Name: BROWN Well #: 8
County: COWLEY Total Vertical Depth: 3166 feet

Operator License No.: 33608
Op Name: W.D. SHORT OIL CO., LLC
Address: 102 S RIVER RD PO BOX 729
OXFORD, KS 67119

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	9.625	216		175 SX
PROD	4.5	3153	1346	125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/19/2011 8:00 AM
Plug Co. License No.: 34271 Plug Co. Name: KIVETT PLUGGING & PIPE PULLING, INC.
Proposal Rcvd. from: KENNETH KIVETT Company: KIVETT PLUGGING & PIPE PULLI Phone: (580) 363-3036

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 10/20/2011 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 3150', CONSOLIDATED WELL SERVICES MIXED & PUMPED 20 SX CLASS A COMMON 2% CC AND DISPLACED IN CASING. TAGGED CEMENT @ 2900'. CUT CASING @ 1511', & 1346', LAYED DOWN 46 JOINTS 4-1/2" CASING (1346'). RIH W/TBG @ .250', CONSOLIDATED OIL WELL SERVICES MIXED & PUMPED 150 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 10-20-2011, 5:00 PM. CONSOLIDATED CEMENT TICKET # 33279.

Perfs:


Top	Bot	Thru	Comments
3153	3166	OH	

Remarks:

Plugged through: TBG

District: 02

Signed


(TECHNICIAN)

RECEIVED Form CP-2/3
NOV 02 2011 11/03/11
KCC WICHITA

VJK