

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-191-21869-00-00
Spot: W2NWSE Sec/Twnshp/Rge: 27-34S-2E
1996 feet from S Section Line, 2259 feet from E Section Line
Lease Name: NORRISH Well #: 8
County: SUMNER Total Vertical Depth: 3195 feet

Operator License No.: 6044
Op Name: STELBAR OIL CORPORATION, INC.
Address: 1625 N WATERFRONT PKWY
WICHITA, KS 67206

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| SURF | 8.625 | 257 | | 200 SX |
| PROD | 5.5 | 3189 | 320 | 110 SX |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/17/2011 8:00 AM
Plug Co. License No.: 6044 Plug Co. Name: STELBAR OIL CORPORATION, INC.
Proposal Rcvd. from: ROB WILLIAMS Company: STELBAR OIL CORPORATION Phone: (316) 264-8378

Proposed Plugging Method: AS PER KCC RULES & REGS / SAND OR CIBP @ 3075, CEMENT TO SURFACE FROM 307'.

Plugging Proposal Received By: PATRICK SHIELDS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/18/2011 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE SET CIBP @ 3074', DUMP BAILED 2 SXS CEMENT ON TOP. LOADED HOLE TO SURFACE, CUT CASING @ 320', LAYED DOWN 6 JOINTS 5-1/2" CASING. 10/18/2011, RIH W/TBG @ 320, CONSOLIDATED OIL WELL SERVICES MIXED & PUMPED 136 SXS 60/40 POZMIX 4% GEL TO SURFACE. P&A COMPLETE. CEMENT CIRCUALTED. PLUG DOWN 11:00 AM 10-18-2011. CONSOLIDATED CEMENT TICKET #31686.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3124 | 3130 | CSG | |

Remarks:

Plugged through: TBG

District: 02

Signed

Duane Krueger
(TECHNICIAN)

RECEIVED

Form CP-2/3

NOV 02 2011

11/03/11

KCC WICHITA