

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-053-21266-00-00  
Spot: SENESWSW Sec/Twnshp/Rge: 4-17S-8W  
710 feet from S Section Line, 1200 feet from W Section Line  
Lease Name: 7 C FARMS Well #: 1  
County: ELLSWORTH Total Vertical Depth: 3307 feet

Operator License No.: 5259  
Op Name: MAI OIL OPERATIONS, INC.  
Address: 8411 PRESTON RD STE 800  
DALLAS, TX 75225

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	420		

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/12/2011 12:00 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: JAY KRIER Company: SOUTHWIND DRILLING CO. Phone: (620) 617-4477

Proposed Plugging Method: AS PER KCC RULES AND REGULATIONS FOR DRY HOLE, SALT SECTION, SPOT 35 SX @ 1100' THEN SPOT 35 SX @ 750' THEN SPOT 35 SX 50' BELOW SURFACE CASING, THEN 25 SX @ 60' CIRC. TO SURFACE. 20 SX IN RAT HOLE AND 15 SX IN MOUSE HOLE.

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: NONE  
Date/Time Plugging Completed: 10/13/2011 11:00 AM KCC Agent: DAN FOX

Actual Plugging Report:

RIH W/WORK STRING CIRC. HOLE CLEAN @ 3307' SPOT BOTTOM PLUG @ 3224' W/35 SX THEN SET BOTTOM SALT PLUG @ 1100' W/35 SX THEN SPOT 35 SX @ 750' FOR TOP SALT SECTION PLUG THEN SPOT 35 SX @ 470' FOR SURFACE CASING PLUG, 25 SX @ 60' THEN 15 SX FOR RAT HOLE AND NO MOUSE HOLE. 180 SX TOTAL WITH 60/40 POS/MIX WITH 4% GEL. WITH 1/4 LB. OF FLO-SEAL.

Perfs:

Remarks: DRY HOLE, PLUG JOB, RECEIVED PER PHONE CALL INTO BARREL DESK.

Plugged through: TBG

District: 02

Signed \_\_\_\_\_

(TECHNICIAN)

RECEIVED  
Form CP-2/3  
NOV 02 2011 11/03/11  
KCC WICHITA

1/24