

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-30281-00-00
Spot: NWSWNE Sec/Twnshp/Rge: 23-30S-7W
4162 feet from S Section Line, 2310 feet from E Section Line
Lease Name: HUFFORD Well #: 1
County: KINGMAN Total Vertical Depth: 4162 feet

Operator License No.: 33999
Op Name: LINN OPERATING, INC.
Address: 600 TRAVIS STE 5100
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	200		175 SXS CMT
PROD	4.5	4147	1880	100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/15/2011 3:00 PM
Plug Co. License No.: 33925 Plug Co. Name: MOORE, MONTE DBA MONTE MOORE DRILLING
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: _____

Proposed Plugging Method: SAND TO 4100 & 4 SKS, REC PIPE, 35 SX 1250' 35 SX 750', CIRC 250-0'.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 10/05/2011 3:45 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE COVERED WITH SAND TO 4070' & CAPPED WITH 4 SKS CMT. THE CASING WAS RECOVERED FROM 1880' & PULLED TO 1250' WHERE 35 SX OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 750' WHERE 35 SX OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 250' WHERE CMT WAS CIRCULATED TO SURFACE WITH 190 SKS CMT.

Perfs:


Top	Bot	Thru	Comments
4147	4162	CSG	OHIO

Remarks: QUALITY WELL SERVICE

Plugged through: CSG

District: 02

Signed _____



(TECHNICIAN)

RECEIVED

Form CP-2/3

NOV 02 2011

11/03/11

KCC WICHITA

✓