

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-015-30281-00-00  
Spot: SENWSW Sec/Twnshp/Rge: 12-25S-7E  
1668 feet from S Section Line, 4247 feet from E Section Line  
Lease Name: GISH Well #: 3  
County: BUTLER Total Vertical Depth: 2554 feet

Operator License No.: 32702  
Op Name: KUTTER OIL, INC.  
Address: 701 E RIVER ST  
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	170		125 SX
PROD	5.5	2554		100 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/30/2011 8:00 AM  
Plug Co. License No.: 32701 Plug Co. Name: C & G DRILLING, INC.  
Proposal Rcvd. from: TIM GULICK Company: KUTTER OIL Phone: (620) 583-4306

Proposed Plugging Method: SAND @ 2420 W/5 SXS, PULL PIPE, CIRC FROM 250' TO SURFACE / 60/40 POZMIX 4% GEL / AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 10/19/2011 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE, SET CIBP @ 2421', DUMPED BAILED 2 SXS CEMENT ON TOP. PRESSURED CASING, HELD OK. SHOT SQUEEZE HOLES @ 250'-251'. SWEDGED INTO 5-1/2" CASING, CONSOLIDATED OILWELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 125 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. CONSOLIDATED CEMENT TICKET #31619. 10-3-2011, RUN STRING LINE @ 210' DID NOT TAG CEMENT. BACKSIDE STANDING FULL. 10-19-2011, TAGGED CEMENT @ 265'. DUG OUT CELLER AND CUT WINDOW IN CSG, CEMENT @ SURFACE ON BACKSIDE OF 5-1/2" CASING. RIH W/TBG @ 260', CONSOLIDATED OILWELL SERVICES MIXED & PUMPED 20 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 5:00 PM 10-19-2011. CONSOLIDATED OIL WELL SERVICES CEMENT TICKET #33247.

Perfs:


Top	Bot	Thru	Comments
2470	2492	CSG	

Remarks: COMPLIANCE / TA

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

RECEIVED

NOV 02 2011

Form CP-2/3

11/03/11

KCC WICHITA