

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-115-19112-00-02
Spot: SESESE Sec/Twnshp/Rge: 12-19S-2E
319 feet from S Section Line, 422 feet from E Section Line
Lease Name: REMPEL C Well #: 3
County: MARION Total Vertical Depth: 2841 feet

Operator License No.: 30483
Op Name: KREMEIER, LES DBA KREMEIER PROD
Address: 3183 US HWY 56
HERINGTON, KS 67449

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	7	2541		
SURF	10	158		
PROD	7	2830		

Well Type: SWD UIC Docket No: D11230.0 Date/Time to Plug: 10/12/2011 10:00 AM
Plug Co. License No.: 30483 Plug Co. Name: KREMEIER, LES DBA KREMEIER PROD & OPERATING
Proposal Rcvd. from: CHRIS KREMEIER Company: Phone: (785) 366-6957

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/21/2011 12:15 PM KCC Agent: SHANE JONES

Actual Plugging Report:

KREMEIER RAN TUBING TO 1745' CAN NOT GET PAST THIS SPOT. EARLIER IN THE WEEK HAD BROUGHT PART OF THE 7" CASING IN THIS AREA. THEY RAN TUBING TO 1740' CONSOLIDATED TIED ON AND PUMPED 50 SX 60/40 POS W/4% GEL, 3% CC AND 50 LBS POLYFLAK. KREMEIER PULLED TUBING UP TO 400'. CONSOLIDATED RAN ITS WIRE LINE DOWN AND TAGGED PLUG @ 1715'. I HAD THEM LOAD THE HOLE TO SEE IF PLUG IS HOLDING. PLUG HELD. CONSOLIDATED TIED ON TO TUBING AND CIRCULATED CEMENT TO SURFACE WITH 100 SX. KREMEIER PULLED TUBING AND CONSOLIDATED TOPPED OFF W/20 SX. LES KREMEIER HAD A LOG SHOWING CEMENT HAD BEEN CIRCULATED UP THE BACKSIDE PREVIOUSLY BUT THOUGHT MAY HAVE FALLEN BACK 35'. THEY DUG OUT THE SURFACE CASING FULL OF CEMENT. CONSOLIDATED TK #31689. 10/25/11 I CHECKED TOP PLUG 1' DOWN FROM TOP OF CASING.

Perfs:

Top	Bot	Thru	Comments
1822	1842	CSG	
1786	1816	CSG	

Remarks: DK #12-049 COMMISSION ORDER

Plugged through: TBG

District: 02

Signed 

(TECHNICIAN)

RECEIVED

NOV 02 2011

KCC WICHITA

Form CP-2/3

cc to MIC
11/02/11
11/03/11

✓