

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-035-20747-00-00  
Spot: SENWNENE Sec/Twnshp/Rge: 24-32S-4E  
4735 feet from S Section Line, 984 feet from E Section Line  
Lease Name: MAGNUSSON Well #: 3  
County: COWLEY Total Vertical Depth: 2358 feet

Operator License No.: 33277  
Op Name: COOPER, ALBERT L. DBA COOPER SER  
Address: PO BOX 381  
WINFIELD, KS 67156

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	7	200		150 sxs
PROD	4.5	2357		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/11/2011 8:00 AM  
Plug Co. License No.: 33277 Plug Co. Name: COOPER, ALBERT L. DBA COOPER SERVICE CO.  
Proposal Rcvd. from: ALBERT L. COOPER Company: COOPER SERVICE CO Phone: (316) 204-0072

Proposed Plugging Method: AS PER KCC RULES & REGS, SAND BACK @ 2280 W/4 SXS, PERF @ 250' & CIRC CEMENT TO SURFACE. 60/40 POZMIX 4%

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL  
Date/Time Plugging Completed: 08/19/2011 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/WORKSTRING CIRCULATING VARIOUS BRIDGES & HOLE CLEAN @ 2300', LAYED DOWN WORK STRING. 8-12-2011, RIH W/SAND LINE @ 2318', SANDED BACK 50' ABOVE PERF @ 2270', DUMP BAILED 4 SXS CEMENT ON TOP. DUG OUT CELLER AND PIT WORK. 8-19-2011, CUT 4-1/2" CASING @ 420', LAYED DOWN 19 JOINTS 4-1/2" CASING (420'). RIH W/TBG @ 260', BUTLER BROS PUMPED 4 YDS SLURRY MIX LESS THAN 10% SAND FROM 260'-0'. CEMENT CIRCULATED. BUTLER BROS. DANIELS READY MIX CEMENT TICKET # 104997. TAGGED CEMENT @ 38', TOPPED WELL BACK TO SURFACE W/8 SXS CLASS A COMMON. P & A COMPLETE.

Perfs:

Top	Bot	Thru	Comments
2332			CSG

Remarks: COMPLIANCE / 10 YR TA RULE

Plugged through: TBG

District: 02

Signed

  
(TECHNICIAN)

RECEIVED  
NOV 02 2011  
KCC WICHITA  
Form CP-2/3  
11/03/11

✓