

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-26183-00-00
Spot: NENENESW Sec/Twnshp/Rge: 1-11S-18W
2461 feet from S Section Line, 2646 feet from E Section Line
Lease Name: RIDLER.G Well #: SWD #2
County: ELLIS Total Vertical Depth: 2486 feet

Operator License No.: 30537
Op Name: VENTURE RESOURCES, INC.
Address: 2255 S WADSWORTH, STE 205
LAKEWOOD, CO 80227

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	13.37	216		w/225 sxs cmt

Well Type: LH UIC Docket No: _____ Date/Time to Plug: 10/28/2011 12:00 AM
Plug Co. License No.: 33493 Plug Co. Name: AMERICAN EAGLE DRILLING LLC
Proposal Rcvd. from: PETE Company: VENTURE RESOURCES, INC. Phone: (303) 722-2899

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.
Lost hole - 12 1/4" stuck at 2486'.
Top of fish 2232'.
Note: Left 254' of drill collars and bit in hole.

Plugging Proposal Received By: RICHARD WILLIAMS
Date/Time Plugging Completed: 10/28/2011 1:30 AM

WitnessType: NONE
KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

1st. Plug at 2232' w/50 sxs.
2nd. Plug at 1200' w/50 sxs.
3rd. Plug at 620' w/150 sxs.
4th. Plug at 270' w/50 sxs.
5th. Plug at 40' w/20 sxs.
Rathole with 30 sxs.

Perfs:

RECEIVED
NOV 04 2011
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed

Richard Williams

(TECHNICIAN)

CM

✓ Form CP-2/3
11/7/11

OCT 31 2011