

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-20202-00-00
Spot: N2N2SE Sec/Twnshp/Rge: 1-15S-19W
2310 feet from S Section Line, 1320 feet from E Section Line
Lease Name: PFANNENSTIEL B Well #: 3
County: ELLIS Total Vertical Depth: 3667 feet

Operator License No.: 34004
Op Name: SAXON OIL COMPANY
Address: 11111 KATY FWY #900
HOUSTON, TX 77079

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3530		
SURF	8.625	205	0	w/185 sxs cmt
PROD	5.5	3664	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/28/2011 8:45 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: MARK BIEKER Company: SAXON OIL COMPANY Phone: (785) 650-4836

Proposed Plugging Method: Ordered 325 sxs 60/40 pozmix - 4% gel - 500# hulls - 11 sxs gel.
Perfs: 1850' - 1295' - 650'.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/28/2011 1:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 3384' - pumped 10 sxs gel - followed with 50 sxs cement and 200# hulls.
Pulled tubing to 1904' - pumped 100 sxs cement with 200# hulls.
Pulled tubing to 900' - pumped 100 sxs cement - cement circulated.
POOH. Hooked up to casing and pumped 20 sxs cement.
Max. P.S.I. 250#.
Hooked to Braden head and pumped 10 sxs cement.
Max. P.S.I. 500#.

Perfs:

Top	Bot	Thru	Comments
3521	3522		
3423	3424		
3274	3275		

RECEIVED
NOV 04 2011
KCC WICHITA

Remarks: QUALITY WELL SERVICES-TICKET #5321.

Plugged through: TBG

District: 04

Signed Ray A. Dinkel
(TECHNICIAN)

CM

Form CP-2/3

11/7/11

OCT 31 2011