

TO:  
STATE CORPORATION COMMISSIO  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 6720

API Well Number: 15-019-21027-00-00  
Spot: NWSWNWSE Sec/Twnshp/Rge: 1-32S-10E  
1674 feet from S Section Line, 2393 feet from E Section Line  
Lease Name: OLIVER C Well #: 1  
County: CHAUTAUQUA Total Vertical Depth: 2000 feet

Operator License No.: 3591  
Op Name: C & E OIL, LLC  
Address: RR1 BOX 1B2  
MOLINE, KS 67353

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/26/2010 12:00 AM  
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.  
Proposal Rcvd. from: \_\_\_\_\_ Company: \_\_\_\_\_ Phone: \_\_\_\_\_

Proposed Plugging Method: 50' plug at TD, 50' plug at 1100', and 550' to surface.

Plugging Proposal Received By: DUANE SIMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed 04/27/2010 10:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Ran 1" to 2000' gelled hole and spotted 10 sack plug. Pulled 1" out of well. Perforated at 1100' and 550'. Ran 1" back into 1100' and spotted 5 sack plug. Pulled up to 550' and circulated cement to surface. Did not get circulation on backside. Pulled 1" and tried squeezing cement to surface. Pressured up to 900 psi and did not get circulation. A total of 65 sacks of cement were used to plug this well.

RECEIVED

OCT 27 2011

DAS

KCC Chanute Dist. #3

RECEIVED

NOV 04 2011


KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)