

TO:
STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-049-19048-00-00
Spot: SENWNWNW Sec/Twnshp/Rge: 12-31S-8E
4636 feet from S Section Line, 4837 feet from E Section Line
Lease Name: SHRADER Well #: 4
County: ELK Total Vertical Depth: 1730 feet

Operator License No.: 3591
Op Name: C & E OIL, LLC
Address: RR1 BOX 1B2
MOLINE, KS 67353

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/07/2010 8:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: 50' plug at 1730', 50' plug at 900' and 550' to surface.

Plugging Proposal Received By: DUANE SIMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed 06/08/2010 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Ran 1" to 1700' gelled hole and spotted 20 sack plug. Pulled 1" out of well. Perforated at 900' and 550'. Ran 1" back into well to 900' and spotted 20 sack plug. Pulled up to 550' and circulated cement to surface inside and outside of casing. Pulled 1" and topped well off. A total of 137 sacks of cement were used to plug this well.

RECEIVED
OCT 27 2011 DAS
KCC Chanute Dist. #3

RECEIVED
NOV 04 2011
KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed [Signature]
(TECHNICIAN)