

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-147-20135-00-00  
Spot: NWNENW Sec/Twnshp/Rge: 11-5S-20W  
330 feet from N Section Line, 1650 feet from W Section Line  
Lease Name: MITCHELL Well #: 1  
County: PHILLIPS Total Vertical Depth: 3444 feet

Operator License No.: 32819  
Op Name: BAIRD OIL COMPANY LLC  
Address: 113 W MAIN PO BOX 428  
LOGAN, KS 67646

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	233	0	150 SX
PROD	4.5	3442	0	150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/06/2011 8:00 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Revd. from: JIM BAIRD Company: BAIRD OIL COMPANY LLC Phone: (785) 689-7456

Proposed Plugging Method: Ordered 275 sxs 60/40 pozmix - 4% gel - 400# hulls - 8 sxs gel spacer.  
Perforate at 1535' - 925 - 230'.

Plugging Proposal Received By: PAT BEDORE Witness Type: NONE  
Date/Time Plugging Completed: 10/06/2011 2:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3150' - pumped 8 sxs gel spacer - followed with 50 sxs 60/40 pozmix - 4% gel with 200# hulls.  
Pulled tubing to 1540' - pumped 100 sxs 60/40 pozmix - 4% gel with 200# hulls to circulate to surface.  
Pulled all tubing. Topped off 4 1/2" casing with 50 sxs 60/40 pozmix - 4% gel - circulated annulus and casing.  
Hooked to 8 5/8" x 4 1/2" annulus.

Perfs:

RECEIVED  
NOV 04 2011  
KCC WICHITA

Remarks: SWIFT SERVICES, INC.-TICKET #20297.

Plugged through: TBG

District: 04

Signed Pat Bedore  
(TECHNICIAN)

CM

✓ Form CP-2/3  
11/7/11