

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-01376-00-00
Spot: N2SEW Sec/Twnshp/Rge: 14-9S-21W
3630 feet from S Section Line, 3300 feet from E Section Line
Lease Name: HINKHOUSE Well #: 3
County: GRAHAM Total Vertical Depth: 3705 feet

Operator License No.: 34318
Op Name: BEREXCO LLC
Address: 2020 N. BRAMBLEWOOD
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	200	0	150 SX
PROD	5.5	3698	0	150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/07/2011 11:00 AM
Plug Co. License No.: 34318 Plug Co. Name: BEREXCO LLC
Proposal Rcvd. from: DENNIS KIRMER Company: BEREXCO LLC Phone: (785) 628-6101

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 4% gel - 500# hulls.
Tubing and packer stuck at 3536'.
Perforate at 1000' - 1720' - 2250'.
Squeezed from 48' - 78' w/100 sxs; 1586' w/125 sxs; 1600' - 1689' w/150 sxs; 2827' - 2858' w/200 sxs.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/07/2011 1:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3000' - pumped 100 sxs 60/40 pozmix - 4% gel with 300# hulls.
Pulled tubing to 2000' - pumped 100 sxs 60/40 pozmix - 4% gel with 200# hulls.
Pulled tubing to 1000' - pumped 100 sxs 60/40 pozmix - 4% gel to circulate to surface.
Pulled all tubing. Topped off 5 1/2" casing with 20 sxs.
Hooked to 8 5/8" x 5 1/2" annulus - circulated out 5 1/2" casing immediately.

Perfs:

Top	Bot	Thru	Comments
3699	3705		OPEN HOLE
2827	2858		
1600	1689		

RECEIVED
NOV 04 2011
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #38310.

Plugged through: TBG

District: 04

Signed _____

Pat Bedore

(TECHNICIAN)

CM

Form CP-2/3

11/9/11

OCT 18 2011