

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-22310-00-01
Spot: SWNESW Sec/Twnshp/Rge: 32-10S-24W
1650 feet from S Section Line, 3630 feet from E Section Line
Lease Name: STRUSS P Well #: 1
County: GRAHAM Total Vertical Depth: 4018 feet

Operator License No.: 6931
Op Name: BOWMAN OIL COMPANY, A GENERAL
Address: 805 CODELL RD
CODELL, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	258	0	125 SX
TI	2.375	3996		
PROD	4.5	4018	0	150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/25/2011 9:45 AM
Plug Co. License No.: 6931 Plug Co. Name: BOWMAN OIL COMPANY, A GENERAL PARTNERSHIP
Proposal Revd. from: WILLIAM "BILL" BOWMAN Company: BOWMAN OIL COMPANY, A GENE Phone: (785) 434-2286

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 500# hulls.
DV Tool at 2109'.

Plugging Proposal Received By: RAY DINKEL
Date/Time Plugging Completed: 10/25/2011 2:00 PM

Witness Type: COMPLETE (100%)
KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 3810' - pumped 100 sxs cement with 150# hulls.
Pulled tubing to 2300' - pumped 100 sxs cement with 150# hulls.
Pulled tubing to 800' - pumped 65 sxs cement - cement circulated.
POOH. Topped off with 20 sxs cement.
Hooked up to Braden head and pumped 10 sxs cement.
Max. P.S.I. 150#. S.I.P. 150#.

Perfs:

Top	Bot	Thru	Comments
3987	3990		LKC - K
3948	3952		LKC - I
3821	3823		
3809	3811		

RECEIVED
NOV 04 2011
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #036025.

Plugged through: TBG

District: 04

Signed

Ray A. Dinkel

(TECHNICIAN)

CM

Form CP-2/3

11/7/11

OCT 26 2011