

15-169-00240-0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 16 1964
4-16-64
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Chas. J. Johnson & H. J. Plouffe

Complete Address: 523 N. Kansas, McPherson, Kansas 67460

Lease Name Knopf Well No. 1

Location NE NE NW Sec. 23 Twp. 15S Rge. 1 (E)/(W)

County McPherson Saline Total Depth 2627'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Blackstone Drilling Co.

Address: 523 N. Kansas, McPherson, Kansas 67460 License No. Rotary

Operation Completed: Hour 2; PM Day 10 Month 4 Year 64

The Above well was plugged as follows:

Filled hole w/ 36 vis mud from T.O. 2627' back to 130'. Set 1/2 sack hulls a halco plug
and 20 sax cement from 120' back to 80'. Filled hole w/ 36 vis mud from 80' back to 40'.
Set 1/4 sack hulls a halco plug and 10 sax cement from 35' back to 3' below ground level.
Filled rat hole w/ mud and 2 sax cement 3' below ground level. 8 5/8" surface pipe 3'
below ground level.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 4/16/64
INV. NO. 8991-W

Signed: [Signature]
Well Plugging Supervisor