


15-169-00053-0001

Form CP-3
Rev. 6-26-62

 KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

APR 9 1963

4-9-63

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name George Hess

Complete Address: 505 N. Charles, McPherson, Kansas

Lease Name George Hess Well No. 1

Location NW NE NE Sec. 31 Twp. 15 Rge. 1 (E) (W) X

County Saline Total Depth 2710'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: Wash down

Plugging Contractor: Art Lamb Casing Pulling Co.

Address: Box 983, Hutchinson, Kansas License No. 440

Operation Completed: Hour 10 AM Day 29 Month March Year 1963

The Above well was plugged as follows:

Hole filled with sand to 2695' and cemented with 5 sacks.

Hole filled with mud to 165'. Rock bridge set from 165' to 155' and

hole cemented with 20 sacks. Hole filled with mud to 40'. Rock bridge

set from 40' to 30' and hole cemented to base of cellar with 10 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: 
Well Plugging Supervisor

DATE 4/8/63

INV. NO. 6858-W