

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-169-20, 253-0000

NE, Sec. 33, T 15 S, R 1 W

2970 feet from (S) section line

1320 feet from (E) section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5120

Lease Name Stein Well # 1

Operator: Range Oil Company, Inc.  
Name & Address 240 Page Court, 220 W. Douglas  
Wichita, Kansas 67202

County Saline

Well Total Depth 2675 feet 86.94

Conductor Pipe: Size \_\_\_\_\_ feet \_\_\_\_\_

Surface Casing: Size 8 3/4 feet 218

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Range Drilling Company, Inc. License Number 5124

Address 240 Page Court, 220 W. Douglas, Wichita, Kansas 67202

Company to plug at: Hour: 5:00 P Day: 12 Month: July Year: 1984

VERBAL PLUGGING ORDERS GIVEN TO Clifford Camp

(company name) Range Drilling Company, Inc. (phone) 316-221-6345

were: Fill hole with heavy mud. Pump 60 sacks cement through drill pipe @ 310'. Fill hole with mud to 60'. Push plug and 1/2 sack hulls to 60' and cement hole to base of cellar with 25 sacks cement. Cement rat hole with 10 sacks

Signed Jack Valley  
Jack Valley  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 7:45 P Day: 12 Month: July Year: 1984

ACTUAL PLUGGING REPORT Hole Filled with heavy mud. 60 sacks 50/50 Pozmix w/ 2% gel pumped through drill pipe @ 310'. Fluid standing @ 10'. Pushed wood/rubber plug to 60' and circulated cement to cellar through drill pipe. Lay down pipe and filled hole. Cemented rat hole with 10 sacks cement through 1 joint drill pipe.

Remarks: TD Formation: Mississippi  
Halliburton Co. Ticket # 748994

I hereby certify that the above plugging instructions were given as herein stated and that I (did / ~~did not~~) observe this plugging.

RECEIVED  
STATE CORPORATION COMMISSION  
Signed Jack Valley  
(TECHNICIAN)

JUL 17 1984  
7-17-84  
CONSERVATION DIVISION  
Wichita, Kansas

FORM CP-2/3  
Rev. 9-82  
ml

INVOICED  
DATE 7-30-84  
INV. NO. 2758  
7-12