

ep

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

15-115-01603-0000

APR 16 1964
4-16-64
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Roland Jones

Complete Address: 109 S. Main, McPherson, Kansas

Lease Name Spach k Well No. 4

Location N 1/4 S 1 Sec. 32 Twp. 18 Rge. 4 (E) (W)

County Marion Total Depth 2495'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Slusser Drilling Co,

Address: P.O. Box 275, Marion, Kansas License No. 59

Operation Completed: Hour 5:30 PM Day 11 Month 4 Year 64

The Above well was plugged as follows:

Filled hole w/ sand from T.D. 2495' back to 2375'. Ran 5 sac cement w/ dump bailer.

Shot off and pulled 5 1/2" casing. Filled hole w/ mud from 2340' back to 170'. Set a 10'

rock bridge and ran 20 sac cement from 160' back to 90'. Filled hole w/ mud from 90'

back to 35'. Set a 5' rock bridge and ran 8 sac cement from 30' back to zero 3' below

ground level. 8 5/8" surface pipe 3' below ground level.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Ronald W. Jones
Well Plugging Supervisor

DATE 4-16-64

INV. NO. 9391-E