

Notice: Fill out COMPLETELY  
and return to Conservation Division at  
the address below within  
60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 5225  
Name: Quinque Operating Company  
Address 1: 908 NW 71st St.  
Address 2: \_\_\_\_\_  
City: Oklahoma City State: OK Zip: 73116 + \_\_\_\_\_  
Contact Person: Catherine Smith  
Phone: (405) 840-9876  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
\_\_\_\_\_ Depth to Top: 5374 Bottom: 5380 T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: 5953 Bottom: 5960 T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 119-20466-00-00  
Spot Description: NE SW SE  
NE SE Sec. 26 Twp. 34 S. R. 30  East  West  
860 Feet from  North /  South Line of Section  
1,967 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Meade  
Lease Name: Adams Well #: 1-26  
Date Well Completed: \_\_\_\_\_  
The plugging proposal was approved on: 8/25/2011 (Date)  
by: \_\_\_\_\_ (KCC District Agent's Name)  
Plugging Commenced: 9/21/2011  
Plugging Completed: 9/23/2011

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8 5/8	1536	0
		Production	4 1/2	6100	1750

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Pumped 40 bbls. of mud down casing. TIH with tubing and CIBP. Set CIBP @ 5324'. Pumped 10 sacks of cement on top. Shot 4 1/2" casing @ 1750'. Laid down same. TIH with tubing to 1536'. Pumped mud and 300 lbs. of cottonseed hulls. Pumped 50 sacks of cement @ 1536'. TOH to 600'. Pumped 50 sack of cement. TOH to 60'. Pumped 20 sacks of cement. Cut off wellhead 4' below ground level. Weld ID plate. Clean location.

Plugging Contractor License #: 33311X Name: Phil Dollar Oilfield Services  
Address 1: P.O. Box 744 Address 2: \_\_\_\_\_  
City: Perryton State: TX Zip: 79070 + \_\_\_\_\_  
Phone: (806) 435-3373  
Name of Party Responsible for Plugging Fees: Quinque Operating Company  
State of Oklahoma County, Oklahoma, ss.  
Catherine Smith (Print Name)  Employee of Operator or  Operator on above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Catherine Smith

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED  
OCT 20 2011  
KCC WICHITA