

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION

WELL PLUGGING RECORD

K.A.R. 82-3-117

Form CP-4 March 2009 Type or Print on this Form Form must be Signed All blanks must be Filled

OPERATOR: License #: 5259 Name: MALOIL OPERATIONS, INC Address 1: 8411 PRESTON RD STE 800 Address 2: City: DALLAS State: TX Zip: 75225 + 5520 Contact Person: ALLEN BANGERT Phone: (214) 219-8883

Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic Water Supply Well Other: SWD Permit #: ENHR Permit #: Gas Storage Permit #: Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet) Depth to Top: Bottom: T.D. Depth to Top: Bottom: T.D. Depth to Top: Bottom: T.D.

API No. 15 - 15-053-21266-00-00

Spot Description: SE NE SW SW Sec. 4 Twp. 17 S. R. 8 East West 710 Feet from North South Line of Section 1,200 Feet from East West Line of Section

Footages Calculated from Nearest Outside Section Corner: NE NW SE SW

County: ELLSWORTH

Lease Name: 7 C FARMS Well #: 1

Date Well Completed: 10/13/2011

The plugging proposal was approved on: 10/13/2011 (Date)

by: VIRGIL CLOTHIER (KCC District Agent's Name)

Plugging Commenced: 10/13/2011

Plugging Completed: 10/13/2011

Show depth and thickness of all water, oil and gas formations.

Table with 6 columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface, Conductor & Production) (Casing, Size, Setting Depth, Pulled Out). Row 1: SURFACE, 8 5/8, 420.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Plugged well with 180 sacks of 60/40 Poz, 4% gel, 1/4# flo-seal, 1st plug @ 3224' with 35 sacks, 2nd plug @ 1100' with 35 sacks, 3rd plug @ 750' with 35 sacks, 4th plug @ 470' with 35 sacks, 5th plug @ 60' to surface with 25 sacks, 15 sacks for rat hole, by Quality (Ticket #5223), plug was down @ 11:00 pm on 10/13/2011.

Plugging Contractor License #: 33350 Name: SOUTHWIND DRILLING, INC

Address 1: 8 NORTH MAIN Address 2: PO BOX 276

City: ELLINWOOD State: KANSAS Zip: 67526 +

Phone: (620) 564-3800

Name of Party Responsible for Plugging Fees: MALOIL OPERATIONS, INC

State of KANSAS County, BARTON, ss.

JILL WAHLMEIER (Print Name) Employee of Operator or Operator on above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Jill Wahlmeier

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED OCT 20 2011 KCC WICHITA



Southwind Drilling, Inc.
Plugging Orders & Reports

Lease: 7 C Farms

Plugging Received from KCC Representative:

Name: Virgil Clothier Date: 10-1-11 Time: 3:30

1st plug @ 3224 feet, 35 sacks Stands 52

2nd plug @ 1100 feet, 35 sacks Stands 17 1/2

3rd plug @ 750 feet, 35 sacks Stands 12

4th plug @ 470 feet, 35 sacks Stands 7 1/2

5th plug @ 60 feet, 25 sacks Stands 1

Mousehole: _____ sacks

Rathole: 15 sacks

Total Cement Used: 180 sacks

Type of cement: 60/40 Poz. 4 1/2 Gal 1/4" Flo Seal

Plug Down @ 11:00 A:m 10-13-11

Call KCC When Completed:

Name: Duane Krueger Date: 10-14-11 Time: 9:25

RECEIVED
OCT 20 2011
KCC WICHITA