

Notice: Fill out COMPLETELY
and return to Conservation Division at
the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 34360
Name: EC Services, LLC
Address 1: P.O. Box 543
Address 2: _____
City: Benton State: KS Zip: 67017 + 0543
Contact Person: Echo Cook
Phone: (316) 295-0207
Type of Well: (Check one) ☐ Oil Well ☐ Gas Well ☐ OG ☐ D&A ☐ Cathodic
☐ Water Supply Well ☐ Other: _____ ☒ SWD Permit #: D-20978
☐ ENHR Permit #: _____ ☐ Gas Storage Permit #: _____
Is ACO-1 filed? ☒ Yes ☐ No If not, Is well log attached? ☐ Yes ☐ No
Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 159-21144-0001
Spot Description: SW NE NW NE
~~SW NE NW NE~~ Sec. 22 Twp. 20 S. R. 10 ☐ East ☒ West
4,850 4904 Feet from ☐ North / ☒ South Line of Section
3,638 1673 Feet from ☒ East / ☐ West Line of Section
GPS-RCC
Footages Calculated from Nearest Outside Section Corner:
☐ NE ☐ NW ☒ SE ☐ SW
County: Rice
Lease Name: Madden Well #: 1
Date Well Completed: 12/20/1981
The plugging proposal was approved on: 9/22/11 (Date)
by: Virgil Clothier (KCC District Agent's Name)
Plugging Commenced: 10/3/11
Plugging Completed: 10/4/11

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8.625	260	0
		Tubing	3.5	3943	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran tubing and mixed 35 sax cement on bottom. Let set up over night. Tagged cement @ 2367'. Perf fiberglass @ 1300'. Run tubing to 1300' and spot 35 sax cement. Let set up. Tagged cement @ 1200'. Perf fiberglass @ 900'. Run tubing to 900' and spot 35 sax cement. Perf fiberglass @ 310'. Run tubing to 330' and circulate 135 sax cement up through 8 5/8". Cement fell. Topped off cellar and fiberglass with 25 sax cement. Job complete
Total cement - 265 sax common cement

Plugging Contractor License #: 3004 Name: Gressel Oil Field Service LLC
Address 1: P.O. Box 438 Address 2: _____
City: Haysville State: KS Zip: 67060 + _____
Phone: (316) 524-1225
Name of Party Responsible for Plugging Fees: EC Services LLC
State of Kansas County: Butler, ss.
ECHO COOK ☐ Employee of Operator or ☒ Operator on above-described well,
(Print Name)
being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.
Signature: _____

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
NOV 01 2011
KCC WICHITA

COPELAND

Acid & Cement

BURRTON, KS ♦ GREAT BEND, KS
(620) 483-5161 (620) 793-3366
FAX (820) 483-2104 FAX (620) 793-3536

POST OFFICE BOX 438
HAYSVILLE, KS 67060
(316) 524-1225
(316) 524-1027 FAX

Invoice

Page: 1

INVOICE NUMBER:
C37793-IN

BILL TO:

EC SERVICES, LLC
P.O. BOX 543
BENTON, KS 67017

LEASE: MADDEN 1 SWD

DATE	ORDER	SALESMAN	ORDER DATE	PURCHASE ORDER	SPECIAL INSTRUCTIONS	
10/14/2011	C37793		10/03/2011		NET 30	
QUANTITY	U/M	ITEM NO./DESCRIPTION		D/C	PRICE	EXTENSION
		10/311				
1.00	EA	CEMENT PUMP CHARGE		0.00	650.00	650.00
20.00	SAX	COMMON CEMENT		0.00	11.25	225.00
67.00	MI	CEMENT MILEAGE PUMP TRUCK		0.00	4.00	268.00
134.00	MI	MILEAGE ROUND TRIP		0.00	2.00	268.00
		10/4/11				
1.00	EA	CEMENT PUMP CHARGE		0.00	650.00	650.00
245.00	SAX	COMMON CEMENT		0.00	11.25	2,756.25
6.00	HR	OVERAGE OF 4 HR MIN		0.00	100.00	600.00
265.00	EA	BULK CHARGE		0.00	1.25	331.25
834.49	MI	BULK TRUCK - TON MILES		0.00	1.10	917.94
REMIT TO:		COP-B		Net Invoice:		6,666.44
P.O. BOX 438		FUEL SURCHARGE IS NOT TAXABLE AND IS ADDED TO		RICCO Sales Tax:		138.70
HAYSVILLE, KS 67060		MILEAGE, PUMP AND OR DELIVERY CHARGES ONLY.		Invoice Total:		6,805.14
RECEIVED BY		NET 30 DAYS				

RECEIVED
NOV 01 2011
KCC WICHITA

There will be a charge of 1.5% "per month" (18% annual rate) on all accounts over 30 days past due.

Copeland Acid & Cement is a subsidiary of Gressel Oil Field Service

Gressel Oil Field Service reserves a security interest in the goods sold until the same are paid for in full and reserve all the rights of a secured party under the Uniform Commercial Code