

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 3372
Name: Dixon Energy
Address 1: 8100 East 22nd St. N. Bldg. 600, Suite F
Address 2: _____
City: Wichita State: KS Zip: 67226 + _____
Contact Person: Mike Dixon
Phone: (316) 264-9632
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: D-26, 640
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
_____ Depth to Top: 4068 Bottom: 4230 T.D. 4447
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

212590001
API No. 15 - 007-21239-22-01
Spot Description: _____
SW NE NW SE Sec. 28 Twp. 31 S. R. 11 East West
2,289 Feet from North / South Line of Section
1,760 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Barber
Lease Name: Stephenson Well #: 2.SWD
Date Well Completed: _____
The plugging proposal was approved on: 11/23/2009 (Date)
by: Jerry Stapleton (KCC District Agent's Name)
Plugging Commenced: 11/30/2009
Plugging Completed: 12/2/2009

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8 5/8	360	None
		Production	4 1/2	4470	2600

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Bridge plug set at 4020', 2 sx cement with dump bailer, pull casing, run tubing to 1st 660', pump 10 sx gel, 50 sx 60/40 poz 4% gel, 2nd 390' 50 sx, 3rd 60' 20 sx
12/4 - Measured 18 down from surface, fill surface with 2 sx cement

RECEIVED
JAN 08 2010
KCC WICHITA

Plugging Contractor License #: 5105 Name: Clarke Corporation
Address 1: 107 W. Fowler Address 2: P.O. Box 187
City: Medicine Lodge State: Kansas Zip: 67104 + _____
Phone: (620) 886-5665
Name of Party Responsible for Plugging Fees: Dixon Energy
State of Kansas County, Barber, ss.
Mark Morgenstern Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Mark Morgenstern