

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 33999  
Name: Linn Operating, Inc.  
Address 1: 600 Travis, Suite 7000  
Address 2: \_\_\_\_\_  
City: Houston, State: TX Zip: 77002 + \_\_\_\_\_  
Contact Person: Steve Johnson  
Phone: (405) 341-1913  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: D11482  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 075-10064-00-01  
Spot Description: NW SE  
Sec. 18 Twp. 22 S. R. 41  East  West  
2039/2029 Feet from  North /  South Line of Section  
2008/1969 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Hamilton  
Lease Name: HCU 1821-D Well #: SWD  
Date Well Completed: \_\_\_\_\_  
The plugging proposal was approved on: \_\_\_\_\_ (Date)  
by: Jerry Stapleton (KCC District Agent's Name)  
Plugging Commenced: 12-1-09  
Plugging Completed: 12-7-09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
			8-5/8"	124'	None
			4-1/2"	2691'	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Pumped 25 sacks cement with 25# hulls and displaced to 1309'. Pumped 30 sacks cement and 75# hulls, displaced to 1190'. Cement @1079', perforated casing @1072, pumped 90 sacks cement with 50# hulls, displaced with 3 bbls. water, perforated tubing & casing @293', tied onto tubing, pumped 100 sacks cement & circulated to surface, Closed surface in, pumped 50 sacks cement with 50# hulls, tied onto 4-1/2", pumped 35 sacks cement and shut in. Plugging Complete.

Plugging Contractor License #: 31529 Name: Mike's Testing & Salvage, Inc.  
Address 1: P.O. Box 467 Address 2: \_\_\_\_\_  
City: Chase State: Kansas Zip: 67524 + 0467  
Phone: (620) 938-2943  
Name of Party Responsible for Plugging Fees: Linn Operating, Inc.  
State of Kansas County, Rice, ss.  
Mike Kelso  Employee of Operator or  Operator on above-described well,  
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Mike Kelso

RECEIVED  
JAN 07 2010

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

KCC WICHITA