

RECEIVED

JAN 28 2010

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

KCC WICHITA Form CP-4 March 2009 Type or Print on this Form Form must be Signed All blanks must be Filled

OPERATOR: License #: 5447 Name: Oxy USA, Inc Address 1: P.O. Box 2528 Address 2: City: Liberal State: KS Zip: 67905+ Contact Person: Kenny Andrews Phone: (620) 629 4200 Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic Water Supply Well Other: SWD Permit #: ENR Permit #: E-27,801 Gas Storage Permit #: Is ACO-1 filed? Yes No If not, is well log attached? Yes No Producing Formation(s): List All (if needed attach another sheet) Chester Depth to Top: 6545 Bottom: 6563 T.D. 6800

API No. 15 - 189-20528-0001 Spot Description: NE 35 Sec. 35 Twp. 34 S. R. 35 East West 1980/1989 Feet from North South Line of Section 660 677 Feet from East West Line of Section Footages Calculated from Nearest Outside Section Corner: NE NW BE SW County: Stevens Length Name: Kinney Chester Sand Unit 1002W Date Well Completed: The plugging proposal was approved on: 1-4-10 (Date) by: Ken Jehlik (KCC District Agent's Name) Plugging Commenced: 1-5-10 Plugging Completed: 1-8-10

Show depth and thickness of all water, oil and gas formations.

Table with 6 columns: Oil, Gas or Water Records (Formation, Content), Casing Record (Surface, Conductor & Production) (Casing, Size, Setting Depth, Pulled Out). Rows show casing sizes 8 5/8, 5 1/2, and 2 3/8 with corresponding setting depths and pulled out measurements.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Oxy set CIBP in 2 3/8 @ 2675'. Cut 2 3/8 @ 2611. Circ. hole w/mud + mixed 25 sx in 5 1/2 from 2611 to 2411. Casing leak had been perf. + squeezed @ 1592 w/75 sx. Ran 2 3/8 to 1700. Mixed 20 sx plug in 5 1/2 from 1700 to 1540. Pull 5 1/2. Ran 2 3/8 to 1372. Circ w/mud + mixed 30 sx plug 1372 to 1272 40 sx 600 to 480 10 sx 40 to 0 Capped 8 5/8 3 ft. below G.L.

Plugging Contractor License #: 31151 Name: Sargent + Horton Plugging Inc. Address 1: Rt 1 Box 49 BA Address 2: City: Tyrone State: OK Zip: 73951 + 9731 Phone: (580) 854 6515

Name of Party Responsible for Plugging Fees: Oxy USA, Inc. 1701 N. Kansas Rd Box 2528 Liberal, KS. 67905 State of Kansas County, Seward, Mo. Kenny Andrews (Print Name) Employee of Operator or Operator on above-described well

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God. Signature: Kenny Andrews