

KCC OIL/GAS REGULATORY OFFICES

Date: 10/14/11

District: 1

Case #: _____

- New Situation
- Response to Request
- Follow-Up

- Lease Inspection
- Complaint
- Field Report

Operator License No: 4058
Op Name: American Warrior, Inc.
Address 1: 3118 Cummings Rd.
Address 2: P.O. Box 399
City: Garden City
State: KS Zip Code: 67843 -0399
Operator Phone #: (620) 275-2963

API Well Number: 15-057-20750-00-00
Spot: NE-SE-SW-SW Sec 13 Twp 27 S Rng 22 E / W
568 Feet from N / S Line of Section
1134 Feet from E / W Line of Section
GPS: Lat: 37.69228 Long: 99.68333 Date: 10/14/11
Lease Name: Shomaker C Well #: 3
County: Ford

Reason for Investigation:

Company requested a state witness to the alternate II cementing job.

Problem:

Alternate II cementing requirements have not been met.

Persons Contacted:

Joe Smith.

Findings:

8 5/8" was set @ 430' with 260 sx cement. 5 1/2" was set @ 5793' with 150 sx cement on primary cementing job. Company opened port collar @ 1419'. Swift Services, Inc. pumped 170 sx SMD cement with limited returns. Cement did not circulate.
10/17/11 Steve Durrant witnessed Log Tech's bond log, and found top of cement to be around 550'. Swift Services pumped 15 sx cement down the annulus and pressured to 500#.

Action/Recommendations:

Follow Up Required Yes No

Date: _____

None. Alternate II cementing requirements have been met.

Verification Sources:

Photos Taken: 0

- RBDMS
- T-I Database
- Other: On-site witness.
- KGS
- District Files
- TA Program
- Courthouse

By: Eric McLaren
Eric McLaren

Retain 1 Copy District Office
Send 1 Copy to Conservation Division

RECEIVED

NOV 18 2011

KCC WICHITA