

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-30096-00-00
Spot: SWNWSW Sec/Twnshp/Rge: 26-12S-22W
1650 feet from S Section Line, 330 feet from W Section Line
Lease Name: STECKLINE JF Well #: 2-4
County: TREGO Total Vertical Depth: 4048 feet

Operator License No.: 6569
Op Name: CARMEN SCHMITT, INC.
Address: PO BOX 47
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3950		
SURF	9.625	325	0	165 SX
LI	5.5	3927	0	325 SX
PROD	7	4028	0	150 SXS

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/15/2011 10:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: FRANCIS HITSCHMANN Company: CARMEN SCHMITT, INC. Phone: (620) 793-5100

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 400# hulls - 15 sxs gel.
Shoot perms 1767' - 960' - 315'.
5 1/2" liner cwc.
DV Tool at 1772' w/310 sxs cement.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/15/2011 2:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3894' - pumped 15 sxs gel - followed with 50 sxs cement and 100# hulls.
Pulled tubing to 1815' - pumped 170 sxs cement - good circulation of cement.
Pulled tubing out - topped off with 30 sxs cement - full.
Backside full. S.I.P. 200#.

Perfs:


Top	Bot	Thru	Comments
3695	3698		
3623	3627		

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKE #527.

Plugged through: TBG

District: 04

Signed


(TECHNICIAN)

CM

RECEIVED
NOV 23 2011
KCC WICHITA

NOV 18 2011

Form CP-2/3

11/28/11