

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-01266-00-00
Spot: NESESE Sec/Twnshp/Rge: 26-12S-22W
990 feet from S Section Line, 330 feet from E Section Line
Lease Name: SCOTT CHAS Well #: 2
County: TREGO Total Vertical Depth: 4030 feet

Operator License No.: 6569
Op Name: CARMEN SCHMITT, INC.
Address: PO BOX 47
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	10.75	513	0	250 SX
PROD 7		4025	0	225 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/10/2011 9:30 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: CURTIS HITSCHMAN Company: CARMEN SCHMITT, INC. Phone: (620) 793-5100

Proposed Plugging Method: Ordered 600 sxs 60/40 pozmix - 4% gel - 600# hulls.
Shoot perms at 950' and 505'.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/10/2011 1:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 1540'. Casing separated - could not get down - went outside the casing.
Tied onto tubing - pumped 275 sxs cement - good circulation.
Pulled tubing out - tied onto 7" casing - squeezed with 325 sxs cement - of that it took 135 sxs to circulate out the backside.
Pumped a total of 600 sxs cement down the well.

Perfs:

Top	Bot	Thru	Comments
3992	3998		ARBUCKLE (OPEN)

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #171

Plugged through: TBG

RECEIVED
NOV 23 2011
KCC WICHITA

District: 04

Signed _____

(TECHNICIAN)

CM

Form CP-2/3

✓ 11/28/11

NOV 18 2011