

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-21800-00-00  
Spot: S2SESENE Sec/Twnshp/Rge: 6-11S-20W  
2819 feet from S Section Line, 442 feet from E Section Line  
Lease Name: RICHARDS Well #: 1  
County: ELLIS Total Vertical Depth: 3710 feet

Operator License No.: 5259  
Op Name: MAI OIL OPERATIONS, INC.  
Address: 8411 PRESTON RD STE 800  
DALLAS, TX 75225

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3660		
SURF	8.625	310	0	225 SX
PROD	5.5	3708	0	175 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/15/2011 9:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: ALLEN BANGERT Company: MAI OIL OPERATIONS, INC. Phone: (785) 483-1676

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 700# hulls - 10 sxs gel.  
Well had many squeezes.  
Emergency plug with rig over the hole.

Plugging Proposal Received By: CASE MORRIS Witness Type: NONE  
Date/Time Plugging Completed: 11/15/2011 11:00 AM KCC Agent: PAT STAAB

Actual Plugging Report:

11/14/2011 - Superior perfed at 350' & 1900'.  
11/15/2011 - RIH with tubing to 3300' - pumped 10 sxs gel - followed with 75 sxs cement with 400# hulls.  
Pulled tubing to 1900' - pumped 100 sxs cement with 200# hulls.  
Pulled tubing to 900' - circulated with 100 sxs cement and 100# hulls.  
Topped off 5 1/2" casing with 10 sxs.  
8 5/8" instant pressure to Max. P.S I. 500#.

Perfs:

Top	Bot	Thru	Comments
3664	3669		ARBUCKLE
3649	3653		ARBUCKLE
3350	3527		LANSING

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

(TECHNICIAN)

CM

RECEIVED  
NOV 23 2011  
KCC WICHITA

Form CP-2/3

11/28/11

NOV 21 2011