

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-00815-00-00
Spot: NWSWSW Sec/Twnshp/Rge: 25-12S-22W
990 feet from S Section Line, 4950 feet from E Section Line
Lease Name: CHRISTIAN CHURCH OF OGA Well #: 6
County: TREGO Total Vertical Depth: 4018 feet

Operator License No.: 6569
Op Name: CARMEN SCHMITT, INC.
Address: PO BOX 47
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	324	0	225 SX
PROD	5.5	4004	0	310 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/10/2011 2:30 PM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: CURTIS HITSCHMANN Company: CARMEN SCHMITT, INC. Phone: (620) 793-5100

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 400# hulls - 15 sxs gel.
DV Tool 1762' w/400 sxs.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/10/2011 6:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3950' - pumped 15 sxs gel - followed with 50 sxs cement with 100# hulls.
Pulled tubing to 1811' - pumped 180 sxs cement - good circulation.
Pulled tubing out - topped off with 20 sxs cement.
Tied onto backside - pumped 10 sxs cement.
S.I.P. 200#.

Perfs:

Top	Bot	Thru	Comments
5115	5129		ARBUCKLE (OPEN
4004	4018		ARBUCKLE

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #172.

Plugged through: TBG

RECEIVED
NOV 23 2011
KCC WICHITA

District: 04

Signed [Signature]
(TECHNICIAN)

CM

Form CP-2/3

11/23/11

NOV 18 2011