

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-00811-00-00
Spot: N2SWNWSW Sec/Twnshp/Rge: 25-12S-22W
1750 feet from S Section Line, 4950 feet from E Section Line
Lease Name: CHURCH OF OGALLAH Well #: 7-2
County: TREGO Total Vertical Depth: 4041 feet

Operator License No.: 6569
Op Name: CARMEN SCHMITT, INC.
Address: PO BOX 47
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	516	0	350 SX
PROD	5.5	4041	0	175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/14/2011 12:00 PM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Revd. from: CURTIS HITSCHMANN Company: CARMEN SCHMITT, INC. Phone: (620) 793-5100

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 400# hulls - 15 sxs gel.
Shoot perfs at 1765' - 1007' - 510'.
Squeezed leak at 1485' w/200 sxs.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/14/2011 5:15 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Shot perfs at 1765' - 1007' - 510'.
Ran tubing to 3940' - pumped 15 sxs gel - followed with 50 sxs cement and 100# hulls.
Pulled tubing to 1800' - pumped 75 sxs cement.
Pulled tubing to 1030' - pumped 50 sxs cement.
Pulled tubing to 550' - pumped 55 sxs cement - had to stop cement - coming out of the hole.
Pulled tubing - topped off casing with 20 sxs cement - full.

Perfs:


Top	Bot	Thru	Comments
3998	4016		ARBUCKLE (OPEN)

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #526.

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

RECEIVED
NOV 23 2011
KCC WICHITA

Form CP-2/3

✓ 11/28/11

NOV 18 2011