

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-055-21295-00-00  
Spot: NWNWSW Sec/Twnshp/Rge: 8-26S-33W  
2310 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: STONE Well #: 1  
County: FINNEY Total Vertical Depth: 5300 feet

Operator License No.: 3842  
Op Name: LARSON ENGINEERING, INC. DBA LAR  
Address: 562 W STATE RD 4  
OLMITZ, KS 67564

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4525		WITH 2 SX CMT
SURF	8.625	1896		WITH 800 SX CMT
PROD	5.52	4760	1940	WITH 175 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/28/2011 1:30 PM

Plug Co. License No.: 32592 Plug Co. Name: WILD WEST WELL SERVICE, INC.

Proposal Rcvd. from: JOHN DAVIDSON Company: WILD WEST WELL SERVICE, INC. Phone: (785) 798-0315

Proposed Plugging Method: SET ICBP @ 4525' WITH 2 SX CMT. SHOOT CASING & POOH WITH CASING. RIH W/TBG TO 1930' & PUMP 50 SX CMT. PLUG AT 930' WITH 50 SX CMT. FILL HOLE FROM 60' TO SURFACE.

Plugging Proposal Received By: KEN JEHLIK

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 10/28/2011 4:30 PM

KCC Agent: JACK MACCLASKEY

Actual Plugging Report:

SET CIBP @ 4525' WITH 2 SX CMT. SHOOT 5 1/2" CASING AT 2400'. UNABLE TO PULL. SHOT 5 1/2" CASING @ 1940' & POOH. 1ST PLUG RIH W/TBG TO 1926' & PUMP 50 SX CMT. 2ND PLUG AT 920' WITH 50 SX CMT. 3RD PLUG FILL HOLE FROM 60' TO SURFACE WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4552	4562		MARMATON

RECEIVED  
NOV 23 2011  
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT CEMENTERS.

Plugged through: TBG

District: 01

Signed

Jack Macclaskey  
(TECHNICIAN)

RECEIVED

NOV - 9 2011

KCC DODGE CITY

Form C-79

11/28/11