

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-01813-00-00
Spot: NESESE Sec/Twnshp/Rge: 36-10S-21W
990 feet from S Section Line, 330 feet from E Section Line
Lease Name: TRICO UNIT WEST Well #: 105
County: GRAHAM Total Vertical Depth: 3715 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	240	0	175 SX
PROD	5.5	3703	0	175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/17/2011 10:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: JOEL STULL Company: VESS OIL CORPORATION Phone: (785) 885-8240

Proposed Plugging Method: Ordered 425 sxs 60/40 pozmix - 4% gel - 500# hulls.
Junk in the hole at 3377'.
Squeezed 2843' - 2875' w/100 sxs; 1116' w/400 sxs.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/17/2011 1:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3362' - pumped 180 sxs 60/40 pozmix - 4% gel with 300# hulls.
Pulled tubing to 1500' - pumped 135 sxs 60/40 pozmix - 4% gel with 200# hulls to circulate to surface.
Pulled all tubing. Topped off 5 1/2" casing with 15 sxs 60/40 pozmix - 4% gel.
Hooked to 8 5/8" x 5 1/2" annulus. Pressured to 200# immediately.

Perfs:

Top	Bot	Thru	Comments
3703	3715		ARBUCKLE
3436	3616		LKC

Remarks: ALLIED CEMENTING COMPANY-TICKET #35932.

Plugged through: TBG

District: 04

Signed _____

Pat Bedore

(TECHNICIAN)

CM

RECEIVED
NOV 23 2011
KCC WICHITA

Form CP-2/3

✓ 11/28/11

NOV 21 2011