

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-081-21682-00-00  
Spot: NWSESWW Sec/Twnshp/Rge: 8-30S-33W  
445 feet from S Section Line, 758 feet from W Section Line  
Lease Name: WINTER Well #: 15-M8-30-33  
County: HASKELL Total Vertical Depth: 5046 feet

Operator License No.: 5447  
Op Name: OXY USA INC.  
Address: 5 E GREENWAY PLZ PO BOX 27570  
HOUSTON, TX 77227

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5000		
SURF	8.625	1703		WITH 725 SX CMT
PROD	5.5	5026	1730	WITH 200 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/01/2011 1:00 PM  
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.  
Proposal Rcvd. from: KIRBY LILLARD Company: SARGENT LILLARD CASING PULL Phone: (580) 251-1881

Proposed Plugging Method: SHOOT TBG AT 3179' & POOH. PERFORATE 5 1/2" CASING @ 3144' & RIH WITH TBG TO 3131' & SPOT 100 SX CMT. LET CMT SET & TAG TOC. SHOOT 5 1/2" CASING & PUMP 50 SX CMT AT 1730', 50 SX CMT AT 650', & 10 SX CMT AT 40'.

Plugging Proposal Received By: JACK MACLASKEY Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/01/2011 4:30 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

\*\*WELL HAS TBG FISH @ 3180\*\* 10/13/11: SHOT TBG OFF AT 3179' & POOH. PERFORATE 5 1/2" CASING AT 3144'. RIH W/ TBG TO 3131' & SPOTTED 100 SX CMT. LET CMT SET & TAG TOC @ 2477'. 11/1/11: 1ST PLUG AT 1730' WITH 50 SX CMT. 2ND PLUG AT 650' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4880	4890		PAWNEE
4670	4674		KC B
4258	4262		KC D
4150	4166		LANSING

Remarks: USED COMMON CEMENY BY SARGENT LILLARD.

Plugged through: CSG

District: 01

RECEIVED

NOV 18 2011

KCC DODGE CITY

Signed

Jack MacLasky  
(TECHNICIAN)

RECEIVED

NOV 23 2011

KCC WICHITA

Form 216-273

11/28/11