

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-081-21345-00-00
Spot: SWNENE Sec/Twnshp/Rge: 26-30S-33W
4024 feet from S Section Line, 1261 feet from E Section Line
Lease Name: MURPHY Well #: 2-26
County: HASKELL Total Vertical Depth: 2765 feet

Operator License No.: 5447
Op Name: OXY USA INC.
Address: 5 E GREENWAY PLZ PO BOX 27570
HOUSTON, TX 77227

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2570		WITH 2 SX CMT
SURF	8.625	644		WITH 295 SX CMT
PROD	4.5	2765	0	WITH 635 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/27/2011 11:00 AM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: KIRBY LILLARD Company: SARGENT LILLARD CASING PULL Phone: (580) 251-1881

Proposed Plugging Method: CIBP @ 2570' & 2 SX CMT. RUN TBG TO 1750' & PUMP 25 SX CMT. PLUG AT 1200' WITH 25 SX CMT. FILL WITH CMT FROM 670'-0'. CHECK BACKSIDE.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/27/2011 4:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 2570' WITH 2 SX CMT. 1ST PLUG AT 1750' WITH 25 SX CMT. 2ND PLUG AT 1200' WITH 25 SX CMT. 3RD PLUG FROM 600'-0' WITH 40 SX CMT. TOOH W/TBG. TOP OFF WITH 6 SX CMT. PUMP 23 SX CMT DOWN ANNULUS TO 300#.

Perfs:

Top	Bot	Thru	Comments
2626	2650		KRIDER

Remarks: USED COMMON CEMENT BY SARGENT & LILLARD.

Plugged through: TBG

RECEIVED
NOV 23 2011
KCC WICHITA

District: 01

Signed

Ken Jehlik
(TECHNICIAN)

RECEIVED
NOV - 4 2011
KCC DODGE CITY

Form CR-27

11/28/11