

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-081-00441-00-00  
Spot: NENENESW Sec/Twnshp/Rge: 9-29S-34W  
2579 feet from S Section Line, 2612 feet from W Section Line  
Lease Name: COLLINGWOOD D F Well #: 3  
County: HASKELL Total Vertical Depth: 2744 feet

Operator License No.: 4824  
Op Name: PIONEER NATURAL RESOURCES USA.  
Address: 5205 N O CONNOR BLVD  
IRVING, TX 75039

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	10.75	654		WITH 100 SX CMT
PROD 7		2534		WITH 125 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/14/2011 3:00 PM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580)251-9618

Proposed Plugging Method: WELL HAS CASING LEAK & FILL TO 1100'. TAG TOP OF FILL & SPOT 60 SX CMT. PRESSURE TEST CASING. IF HOLDS, PERFORATE @ 700' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: KEN JEHLIK Witness Type: PARTIAL  
Date/Time Plugging Completed: 11/15/2011 11:00 AM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

**\*\*WELL HAS CASING LEAK & FILL TO 1100'\*\*** 11/14/11: TAGGED TOP OF FILL AT 1102'. PRESSURED 7" CASING TO 500 PSI. HELD OK. PERFORATED 7" AT 1097'. RIH W/TBG & PACKER, SQUEEZED 60 SX CMT INTOR PERFS. SHUT IN PRESSURE @ 500 PSI. SDON. 11/15/11: TAGGED TOC @ 795'. PRESSURED 7" CASING TO 500 PSI. HELD OK. PERFORATED 7" @ 700'. CIRCULATED 320 SX CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
2524	2534		HERRINGTON
2501	2511		HOLLENBERG

RECEIVED  
NOV 23 2011  
KCC WICHITA

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA HIGH FL\*\* USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

RECEIVED  
NOV 21 2011  
KCC DODGE CITY

Signed

Jack MacLaskey  
(TECHNICIAN)

Form 60-23

11/28/11