

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-081-00537-00-00
Spot: SWSWSWNE Sec/Twnshp/Rge: 9-30S-34W
2540 feet from N Section Line, 2540 feet from E Section Line
Lease Name: KIRKPATRICK J L Well #: 2
County: HASKELL Total Vertical Depth: 2766 feet

Operator License No.: 4824
Op Name: PIONEER NATURAL RESOURCES USA.
Address: 5205 N O CONNOR BLVD
IRVING, TX 75039

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	10.75	614		WITH 100 SX CMT
PROD 7		2531	0	WITH 125 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/04/2011 9:30 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: PERFORATE 7" ABOVE FILL & RIH W/TBG TO 1100' & SQUEEZE 100 SX CMT. TAG TOC & EITHER SHOOT 7" CASING OFF BELOW SURFACE PIPE & PUMP 80 SX CMT AT 650' & FILL HOLE FROM 40' TO SURFACE OR PERFORATE 7" AT 650' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/04/2011 4:30 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

WELL HAS CASING LEAK @ 1500'. TAGGED TOP OF FILL AT 1593'.
PERFORATE 7" @ 1545'. RIH W/TBG & PACKER TO 1100' & PUMPED 100 SX CMT.
PRESSURED TO 1200 PSI. SHUT IN FOR 3 HOURS. TAGGED TOC @ 1186'.
PRESSURE TESTED 7" TO 450 PSI. HELD OK. PERFORATE 7" CASING @ 650'
PUMPED 300 SX CMT CIRCULATING TO SURFACE IN 7" X 10 3/4" ANNULAR.

Perfs:

Top	Bot	Thru	Comments
2738	2748		FT. RILEY
2672	2700		WINFIELD
2624	2654		L. KRIDER
2594	2618		I/ LRODER
2571	2588		HERRINGTON

RECEIVED
NOV 23 2011
KCC WICHITA

Remarks: **COMPLIANCE ISSUE: DENIED TA HIGH FL** USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: CSG

District: 01

Signed

Jack MacLaskey
(TECHNICIAN)

RECEIVED

NOV - 9 2011

KCC DODGE CITY

Form CS-23

11/28/11