

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-179-20329-00-00
Spot: NESENE Sec/Twnshp/Rge: 13-10S-26W
3693 feet from S Section Line, 433 feet from E Section Line
Lease Name: GANO B Well #: 3
County: SHERIDAN Total Vertical Depth: 4080 feet

Operator License No.: 33268
Op Name: RL INVESTMENT, LLC
Address: 217 SAINT PETER ST.
MORLAND, KS 67650

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	218	0	w/150 sxs cmt
PROD	4.5	4079	0	w/225 sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/09/2011 8:00 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Revd. from: LEON PFEIFER Company: RL INVESTMENT, LLC Phone: (785) 627-5711

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 4% gel - 700# hulls.
Plug through tubing.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/09/2011 11:30 AM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 218' w/150 sxs cement.
4 1/2" production casing set at 4079' w/225 sxs cement.
TD 4080'. PBTD 4079'.
Perforated production casing at 2197' and 1335'.
Ran tubing to 3750' - pumped 100 sxs cement with 400# hulls.
Pulled tubing to 2500' - pumped 100 sxs cement with 200# hulls.
Pulled tubing to 1000' - pumped 120 sxs cement with 100# hulls - cement to surface.
Pulled tubing to surface. Topped production casing with 5 sxs cement.
Connected to 8 5/8" surface casing - pumped 50 sxs cement.
Max. P.S.I. 300#.

Perfs:

Top	Bot	Thru	Comments
3814	4043		LKC
3795	3805		TORONTO
1350	2200		

RECEIVED
NOV 23 2011
KCC WICHITA

Remarks: SOS CEMENTING COMPANY-TICKET #543.

Plugged through: TBG

District: 04

Signed Darrel Dipman
(TECHNICIAN)

CM

Form CP-2/3

✓ 11/28/11

NOV 17 2011