

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-165-21319-00-00
Spot: SESENW Sec/Twnshp/Rge: 24-18S-18W
2315 feet from N Section Line, 2311 feet from W Section Line
Lease Name: OBORNY A Well #: 4
County: RUSH Total Vertical Depth: 3755 feet

Operator License No.: 33372
Op Name: FUTURE PETROLEUM COMPANY LLC
Address: 1455 W LOOP S PO BOX 540225
HOUSTON, TX 77254

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3700		WITH 2 SX CMT
SURF	8.625	1124		WITH 425 SX CMT
PROD	5.5	3754	0	WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/13/2011 8:30 AM
Plug Co. License No.: 32970 Plug Co. Name: H-D OILFIELD SERVICE, INC.
Proposal Rcvd. from: TERRY MADDEN Company: FUTURE PETROLEUM Phone: (620) 804-2202

Proposed Plugging Method: SET CIBP @ BOTTOM & 2 SX CMT. PRESSURE CASING. IF IT HOLDS PERFORATE @ 1140' & CIRCULATE CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/13/2011 11:40 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SET CIBP @ 3700' & 2 SX CMT. PERFORATE AT 1140'. TIE ONTO CASING & PRESSURED TO 800#. COULDN'T PUMP INTO. TIED ONTO BACKSIDE & PUMPED 1/4 BBL. PRESSURED TO 800# & HELD. RAN TBG TO 1175' & PUMPED 130 SX CMT. CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3754	3755		ARBUCKLE OPEN

RECEIVED
NOV 23 2011
KCC WICHITA

Remarks: **CCOMPLIANCE ISSUE: DENIED TA HIGH FL** USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

District: 01

RECEIVED
NOV - 4 2011
KCC DODGE CITY

Signed

Michael J. Maier
(TECHNICIAN)

FORM 10-28
11/28/11