

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-165-21544-00-00
Spot: SWSNW Sec/Twnshp/Rge: 24-18S-18W
2988 feet from S Section Line, 3619 feet from E Section Line
Lease Name: OBORNY A Well #: 6
County: RUSH Total Vertical Depth: 3739 feet

Operator License No.: 33372
Op Name: FUTURE PETROLEUM COMPANY LLC
Address: 1455 W LOOP S PO BOX 540225
HOUSTON, TX 77254

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		1202		WITH 2 SX CMT
CIBP		3665		WITH 2 SX CMT
SURF	8.625	1120		WITH 400 SX CMT
PROD	5.5	3734	0	WITH 100 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/14/2011 2:00 PM
Plug Co. License No.: 32970 Plug Co. Name: H-D OILFIELD SERVICE, INC.
Proposal Rcvd. from: TERRY MADDEN Company: FUTURE PETROLEUM Phone: (620) 804-2202

Proposed Plugging Method: SET CIBP @ BOTTOM & 2 SX CMT. PRESSURE CASING. IF HOLDS PERFORATE @ 1140' & CIRCULATE CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/14/2011 3:15 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SET CIBP @ 3665' & 2 SX CMT. PRESSURED CASING & BLED OFF. SET CIBP @ 1202' WITH 2 SX CMT. PRESSURED TO 500# & HELD. PERFORATED @ 1140'. TIED ONTO CASING & PUMPED 300 SX CMT. CMT CIRCULATED TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3734	3739		ARBUCKLE OPEN

RECEIVED
NOV 23 2011
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

District: 01

Signed

Michael Maier
(TECHNICIAN)

RECEIVED

NOV - 4 2011

KCC DODGE CITY

Form CP 2/3

11/28/11