

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-165-21833-00-00
Spot: NWNESENE Sec/Twnshp/Rge: 23-17S-20W
1501 feet from N Section Line, 465 feet from E Section Line
Lease Name: MORAN Well #: 1-23
County: RUSH Total Vertical Depth: 4100 feet

Operator License No.: 9855
Op Name: GRAND MESA OPERATING COMPANY
Address: 1700 N WATERFRONT PKWY BLDG 600
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	596		WITH 375 SX CMT
DVT		1392		WITH 250 SX CMT
PROD	5.5	4098	0	WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/21/2011 1:00 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: JOHN JOHNSON Company: GRAND MESA Phone: (620) 617-3357

Proposed Plugging Method: PUMP 35 SX CMT & 150# HULLS. GEL SPACER TO ANHYDRITE THEN CMT TO SURFACE. TIE ONTO BACKSIDE & PUMP 50 SX CMT IF POSSIBLE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/21/2011 2:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PUMPED 35 SX CMT & 200# HULLS, 18 SX GELLED WATER & 145 SX CMT.
MAXIMUM PRESSURE 1200#. SHUT IN PRESSURE 500#. TIE ONTO BACKSIDE &
PRESSURED TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
3995	4004		
3990	3992		
3983	3986		

RECEIVED
NOV 23 2011
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

District: 01

Signed Michael Maier
(TECHNICIAN)

RECEIVED
OCT 31 2011
KCC DODGE CITY

FORM 15B 2/3
11/28/11