

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-081-20206-00-00
Spot: SESESE Sec/Twnshp/Rge: 26-29S-31W
357 feet from S Section Line, 308 feet from E Section Line
Lease Name: WALDRON Well #: 3
County: HASKELL Total Vertical Depth: 5450 feet

Operator License No.: 6230
Op Name: FIRST NATIONAL OIL, INC.
Address: 1755 S BROADWAY ST STE 6
OVIEDO, FL 32765

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	807		450 SX
PROD	4.5	5448	1788	150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/02/2011 1:00 PM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY WALTERS Company: _____ Phone: (620) 655-4494

Proposed Plugging Method: SET CIBP @ 5260' WITH 2 SX CMT. PLUG AT 1715' WITH 20 SX GEL & 50 SX CMT. PLUG AT 840' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/02/2011 5:30 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

11/1/11: PUMPED 150# HULLS & 40 SX CMT INTO PERFS. SDFN. 11/2/11: TAGGED TOC @ 4500'. SHOT 4 1/2" CASING AT 1788' & POOH WITH CASING. RIH W/TBG TO 1715'. 1ST PLUG AT 1715' WITH 20 SX GEL & 50 SX CMT. 2ND PLUG AT 840' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5342	5350		
5314	5318		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

RECEIVED
NOV 23 2011
KCC WICHITA

District: 01

Signed Jack MacLaskey
(TECHNICIAN)

RECEIVED
NOV 18 2011
KCC DODGE CITY

Form CP 2/3

11/28/11