

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-189-00398-00-00  
Spot: SWSWNE Sec/Twnshp/Rge: 35-33S-36W  
2970 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: HEGER Well #: 1  
County: STEVENS Total Vertical Depth: 2856 feet

Operator License No.: 5208  
Op Name: EXXONMOBIL OIL CORP  
Address: 14950 HEATHROW FORREST PKWY P  
HOUSTON, TX 77210

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	10.75	580		WITH 200 SX CMT
L1	4.5	2518		WITH 21 SX CMT
L2	5.5	2856		
PROD	7	2645	0	WITH 900 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/17/2011 1:00 PM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed  
Plugging  
Method:

PLUG AT 2556' WITH 50 SX CMT. PLUG AT 1860' WITH 25 SX CMT. PLUG AT 630' WITH 40 SX CMT. FILL FROM 40' TO SURFACE.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/17/2011 1:00 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

TBG STUCK IN WELL, CUT TBG AT 2710'. SPOOTED 80 SX CMT & 100# HULLS AT 2700'. SDON. TAGGED TOC @ 1801'. TESTED 4 1/2" CASING TO 1400 PSI. HELD OK. SHOT 4 1/2" CASING AT 1340'. UNABLE TO PULL. TIH W/TBG TO 1800' & SPOTTED 50 SX CMT. TAGGED TOC @ 1050'. PERFORATED 4 1/2" CASING AT 600'. PUMPED INTO 4 1/2" CASING AT 3 BBL PER MINUTE AT 800 PSI WITH NO BLOW OR SUCTION ON 4 1/2" X 7" ANNULAR. PUMPED 75 SX CMT DOWN 4 1/2" CASING WITH A SHUT IN PRESSURE OF 500 PSI. TIED ONTO 4 1/2" X 7" ANNULUS & PRESSURED TO 500 PSI.

Perfs:

Top	Bot	Thru	Comments
2627	2838		

RECEIVED  
NOV 23 2011  
KCC WICHITA

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: CSG

District: 01

RECEIVED  
NOV 21 2011  
KCC DODGE CITY

Signed

Jack MacLasky  
(TECHNICIAN)

Form CS-73

11/28/11