

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-23717-00-00
Spot: W2E2E2SW Sec/Twnshp/Rge: 23-25S-12W
1320 feet from S Section Line, 2240 feet from W Section Line
Lease Name: MCCLURE FARMS Well #: 1
County: STAFFORD Total Vertical Depth: 4280 feet

Operator License No.: 5205
Op Name: MID-CONTINENT ENERGY CORP.
Address: 105 S BROADWAY STE 360
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	313		WITH 450 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 11/10/2011 9:30 AM
Plug Co. License No.: 34541 Plug Co. Name: NINNESCAH DRILLING LLC
Proposal Rcvd. from: RICK BARRIGER Company: NINNESCAH DRILLING LLC Phone: (620) 933-2001

Proposed Plugging Method: 1ST PLUG AT 4200' WITH 50 SX CMT. 2ND PLUG AT 700' WITH 50 SX CMT. 3RD PLUG AT 350' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: JACK MACLASKEY WitnessType: NONE
Date/Time Plugging Completed: 11/10/2011 11:30 AM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

Perfs:

1ST PLUG AT 4200' WITH 50 SX CMT. 2ND PLUG AT 700' WITH 50 SX CMT. 3RD PLUG AT 350' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

RECEIVED
NOV 23 2011
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: DP

District: 01

Signed

Jack MacLaskey
(TECHNICIAN)

RECEIVED

NOV 21 2011

KCC DODGE CITY

Form CS

✓ 11/28/11